Project Name/No.: **Talbot & Willow Bank Stabilization/ 21623**
Bid Opening: **8/6/2026 10:00AM**
Location: **City of Rockland, ME**
ENG/PM: **Ron May / Owen Chaplin**
Engineer's Estimate: **$276,000**

Issuing Office: **Topsham Office**
11 Bowdoin Mill Island, Ste 140
Topsham, ME 04086

BID QUANTITIES				BIDDER'S NAME									
				Whitcomb Contracting									
	Item	Qty.	UNIT	UNIT AMT	BID	UNIT AMT	BID	UNIT AMT	BID	UNIT AMT	BID	UNIT AMT	BID
BASE BID													
1	CLEARING	1	LS	$ 5,000.00	$ 5,000.00		$ -		$ -		$ -		$ -
2	REMOVE BITUMINOUS CONCRETE PAVEMENT	400	SY	$ 3.00	$ 1,200.00		$ -		$ -		$ -		$ -
3	COMMON EXCAVATION	280	CY	$ 40.00	$ 11,200.00		$ -		$ -		$ -		$ -
4	ROCK EXCAVATION - LEDGE	10	CY	$ 275.00	$ 2,750.00		$ -		$ -		$ -		$ -
5	GRANULAR BORROW	210	CY	$ 50.00	$ 10,500.00		$ -		$ -		$ -		$ -
6	SCREENED STONE	9	CY	$ 75.00	$ 675.00		$ -		$ -		$ -		$ -
7	AGGREGATE BASE GRAVEL TYPE A	180	CY	$ 65.00	$ 11,700.00		$ -		$ -		$ -		$ -
8	HOT MIX ASPHALT, 9.5 MM HAND PLACE	50	Tons	$ 350.00	$ 17,500.00		$ -		$ -		$ -		$ -
9	GABION RETAINING WALL	150	CY	$ 350.00	$ 52,500.00		$ -		$ -		$ -		$ -
10	15-INCH HDPE STORM DRAIN PIPE	10	LF	$ 100.00	$ 1,000.00		$ -		$ -		$ -		$ -
11	18-INCH HDPE STORM DRAIN PIPE	15	LF	$ 125.00	$ 1,875.00		$ -		$ -		$ -		$ -
12	60-INCH REINFORCED CONCRETE CULVERT	48	LF	$ 500.00	$ 24,000.00		$ -		$ -		$ -		$ -
13	CULVERT TRASH RACK AND FLARED END TREATMENT	1	LS	$ 8,000.00	$ 8,000.00		$ -		$ -		$ -		$ -
14	CATCH BASIN RISER, FRAME, AND GRATE	1	EA	$ 8,000.00	$ 8,000.00		$ -		$ -		$ -		$ -
15	8-FOOT DIAMETER DRAIN MANHOLE	10	VF	$ 1,000.00	$ 10,000.00		$ -		$ -		$ -		$ -
16	CONNECT STORM DRAIN PIPE INTO GRANITE BLOCK CULVERT	1	LS	$ 3,500.00	$ 3,500.00		$ -		$ -		$ -		$ -
17	4-FOOT DIAMETER CATCH BASIN	8	VF	$ 750.00	$ 6,000.00		$ -		$ -		$ -		$ -
18	ADJUST CATCH BASIN OR MANHOLE TO GRADE	1	EA	$ 1,200.00	$ 1,200.00		$ -		$ -		$ -		$ -
19	SPLIT RAIL FENCE	120	LF	$ 100.00	$ 12,000.00		$ -		$ -		$ -		$ -
20	PLAIN RIPRAP	20	CY	$ 75.00	$ 1,500.00		$ -		$ -		$ -		$ -
21	STREAM RESTORATION	85	LF	$ 100.00	$ 8,500.00		$ -		$ -		$ -		$ -
22	LOAM - 4" DEPTH, SEED, AND MULCH	1,000	SY	$ 7.50	$ 7,500.00		$ -		$ -		$ -		$ -
23	LANDSCAPING	1	LS	$ 45,000.00	$ 45,000.00		$ -		$ -		$ -		$ -
24	HAND LABOR, STRAIGHT TIME	10	HR	$ 70.00	$ 700.00		$ -		$ -		$ -		$ -
25	ALL-PURPOSE EXCAVATOR (INC OPER.)	10	HR	$ 185.00	$ 1,850.00		$ -		$ -		$ -		$ -
26	TRUCK - LARGE (INC OPER.)	10	HR	$ 125.00	$ 1,250.00		$ -		$ -		$ -		$ -
27	MAINTENANCE OF TRAFFIC CONTROL DEVICES	1	LS	$ 1,500.00	$ 1,500.00		$ -		$ -		$ -		$ -
28	TEMPORARY SOIL EROSION & POLLUTION CONTROL	1	LS	$ 7,500.00	$ 7,500.00		$ -		$ -		$ -		$ -
29	DEWATERING & TEMPORARY BYPASSING	1	LS	$ 5,000.00	$ 5,000.00		$ -		$ -		$ -		$ -
30	MOBILIZATION & DEMOBILIZATION	1	LS	$ 6,400.00	$ 6,400.00		$ -		$ -		$ -		$ -
TOTAL BASE BID AMOUNT ITEMS (1 THROUGH 30)					**$275,300.00**		**$ -**		**$ -**		**$ -**		**$ -**

*modified due to mathmatical errors in submitted bid