Project Name/No.: High Road Culvert Replacement/ 21681
Bid Opening: 10/15/2026 10:00 AM
Location: Frenchboro, ME
ENG/PM: B. Springer/J. Wallace

Issuing Office: Topsham Office
11 Bowdoin Mill Island, Ste 140
Topsham, ME 04086

BID QUANTITIES				BIDDER'S NAME Gardner Concrete	
Bid Item No.	Item	Qty.	UNIT	UNIT AMT	BID
BASE BID					
202.202	Removing Pavement Surface	290	SY	$ 10.00	$ 2,900.00
203.25	Granular Borrow	620	CY	$ 80.00	$ 49,600.00
304.1	Aggregate Subbase Course - Gravel	100	CY	$ 100.00	$ 10,000.00
304.14	Aggregate Base Course – Type A	70	CY	$ 125.00	$ 8,750.00
403.207	Hot Mix Asphalt, 19.0 mm Nominal Maximum Size	35	T	$ 500.00	$ 17,500.00
403.208	Hot Mix Asphalt – 12.5 mm Nominal Maximum Size	25	T	$ 500.00	$ 12,500.00
409.15	Bituminous Tack Coat, Applied	10	G	$ 100.00	$ 1,000.00
419.3	Saw Cutting Bituminous Pavement	50	LF	$ 5.00	$ 250.00
502.9	Precast Concrete Inlet Structure	1	LS	$ 40,000.00	$ 40,000.00
502.91	Precast Concrete Inlet Cutoff Wall	1	LS	$ 10,000.00	$ 10,000.00
502.92	Precast Concrete Outlet Headwall	1	LS	$ 25,000.00	$ 25,000.00
511.07	Cofferdam: Upstream and Downstream	1	LS	$ 30,000.00	$ 30,000.00
603.239	48 Inch Culvert Pipe Option III	45	LF	$ 4,000.00	$ 180,000.00
606.1301	31” W-BM Guardrail, Mid-Way Splice Single Faced	100	LF	$ 150.00	$ 15,000.00
606.1305	31” W-BM Guardrail, Mid-Way Splice Flared Terminal	4	EA	$ 10,000.00	$ 40,000.00
610.08	Plain Riprap	130	CY	$ 150.00	$ 19,500.00
610.15	Riprap Remove and Reset	15	CY	$ 100.00	$ 1,500.00
615.07	Loam	30	CY	$ 200.00	$ 6,000.00
618.141	Seeding Method Number 3	3	UN	$ 200.00	$ 600.00
620.63	Non-Woven Geotextile	200	SY	$ 10.00	$ 2,000.00
652.36	Maintenance of Traffic Control Devices	1	LS	$ 20,000.00	$ 20,000.00
656.75	Temporary Soil Erosion and Water Pollution Control	1	LS	$ 10,000.00	$ 10,000.00
659.10	Mobilization	1	LS	$ 14,500.00	$ 14,500.00
			TOTAL BASE BID		$ 516,600.00

1 bid received

WRIGHT-PIERCE
Engineering a Better Environment